



# FUTURE FORMS SYSTEMS

Rebar Coupler  
Prequalification

## Table of Content

Company introduction	2
FUTURE coupler features	3
Standard couplers	4
Installation	5
Cold Forge coupler	7
Cold Forge coupler calculation	8
Product quality certificate	11
Certification	12
Municipality approval	13
Key consultant approval	14
Lab tests results	16
Company information	17

## Introduction

Rebar Couplers are devices used to connect steel bars in reinforced concrete structures that are more beneficial than the conventional method of lap splicing.

**FUTURE Couplers** are the best cost efficient system that guarantees that the ultimate performance of the reinforcement with avoidance of connection failures.

## Benefits

- Every connection is pull tested during the extrusion cycle.
- No reduction of the cross section area of the bar.
- Solves bar congestion problems.
- Shortens construction cycle time.
- Reduces steel wastage.

## FUTURE Coupler features

- Designed and manufactured in compliance with ACI318, BS8110
- Full-Tension splice, bar break under tensile tests.
- Easy to operate and maintain, High production efficiency and fast installation, no need for skilled technicians.
- Several types of splices, which could be suitable for rebar splicing when the rebar cage or the bending rebar is used.
- The splices could be produced in advance without influencing the construction period.
- Inexpensive to purchase, maintain and repair.
- Manufactured under strict quality assurance plans.

## Standard Coupler

### 3 Step process

- **Cutting:** The end of the rebar is sawn cut by special cutting machine for bar splicing.
- **Rolling:** The sawn cut end of the rebar is directly rolled using a thread rolling machine.
- **Splicing:** Connecting rebars using couplers.



## Installation

- For rebars to be connected with standard coupler, the effective threading length of each rebar end should be half of the tube coupler length. (see TABLE-1)
- Tighten the coupler with wrench so that the two threaded rebar ends can push against each other tightly in the middle of the coupler.
- After splicing, the effective screw threads on rebar ends outside the coupler should be no more than two threads on each side

Size	Effective Thread Length (mm)	Wrench Torque Setting (Nm <sup>2</sup> )
Ø 16	22.5	120
Ø 18	25.0	150
Ø 20	27.5	180
Ø 22	30.0	220
Ø 25	32.5	270
Ø 28	35.0	270
Ø 32	40.0	300
Ø 36	40.0	300
Ø 40	50.0	300

(Table 1)




## Standard Coupler



Thread rolling machine





Thread roller



Rib Cutter



Torque Wrench



## Cold forge Coupler

### 3 Step process

- **Cutting:** The end of the rebar is sawn cut by special cutting machine.
- **Cold Forging:** The sawn end of the bar is then enlarged by a cold forging process.
- **Threading:** Thread is mechanically formed onto the enlarged end of the bar.







## Cold Forging coupler calculation

Bar Diameter (mm)	Out Diameter of Coupler (mm)	Length of Coupler (mm)	Thread Size (mm)		Weight of Coupler (kg)
			Direct Rolling	Rolling after Stripping	
16	23	42	M17 x 2.5	M16.5 x 2.5	0.07
18	28	46	M19 x 2.5	M18.5 x 2.5	0.13
20	30	50	M21 x 2.5	M20.5 x 2.5	0.15
22	33	54	M23 x 2.5	M22.5 x 2.5	0.19
25	38	62	M26 x 2.5	M25.5 x 2.5	0.30
28	43	68	M29 x 2.5	M28.5 x 2.5	0.43
32	48	76	M33 x 2.5	M32.5 x 2.5	0.58
36	53	84	M37 x 2.5	M36.5 x 2.5	0.93
40	60	92	M41 x 2.5	M40.5 x 2.5	1.25

## Cold forge Coupler



**Upset Rolling Machine**



# Product quality certificate



**Future Scaffolding And Aluminum Industries LLC.**

Product quality certificate

Date: 01/04/2019


No: 20190104

Product	Specification	Chemical composition								Mechanical Behavior		Process performance	
		C	Si	S	Mn	P	Cr	Ni	Cu	Tensile strength Kn	Yield point Kn	Squash	NDT
Rebar Coupler	Ø 28 x 5.5	0.2	0.27	0.02	1.66	0.02	0.4	0.07	0.06	192	130	Qualified	Qualified

Signature:



# Certification



*Certificate Of Registration*  
Awarded to

**FUTURE SCAFFOLDING AND ALUMINIUM INDUSTRIES LLC**


at  
P.O.BOX NO: 119950, DUBAI INDUSTRIAL CITY, DUBAI, UAE

Quality Registrar Systems certify that the management system of the above organization has been audited and found to be in compliance with the QRS requirements for registration of the management system standard detailed below:



**OHSAS 18001:2007**  
Occupational Health and Safety Management Systems

Scope of work  
ALUMINIUM EXTRUSION, ALUMINIUM FORM WORK, ALUMINIUM SCAFFOLDING,  
ALUMINIUM & STEEL FABRICATION AND METAL COATING

EA 17  
Certificate No: DQU-30221  
Originally Registered: 25 OCT 2016  
Latest Issue: 30 OCT 2018  
Valid up-to: 24 OCT 2019




Quality Registrar Systems



CB-037-MS


**MANAGING OFFICE ADDRESS:**  
Quality Registrar Systems  
P.O. Box :26826  
United Arab Emirates



Tel: +971-2-6714302  
Fax: +971-2-6741449  
www.qrsyst.com

**WORLD WIDE CERTIFICATION**

Quality Registrar Systems is accredited by Dubai Accreditation Department (DAC)  
for the Scope mention on Quality Registrar Systems (QRS) Accreditation Certificate No. CB-037-MS



*Certificate Of Registration*  
Awarded to

**FUTURE SCAFFOLDING AND ALUMINIUM INDUSTRIES LLC**


at  
P.O.BOX NO: 119950, DUBAI INDUSTRIAL CITY, DUBAI, UAE

Quality Registrar Systems certify that the management system of the above organization has been audited and found to be in compliance with the QRS requirements for registration of the management system standard detailed below:




**ISO 9001:2015**  
Quality Management Systems

Scope of work  
ALUMINIUM EXTRUSION, ALUMINIUM FORM WORK, ALUMINIUM SCAFFOLDING,  
ALUMINIUM & STEEL FABRICATION AND METAL COATING

EA 17  
Certificate No: DQU-10431  
Originally Registered: 25 OCT 2016  
Latest Issue: 30 OCT 2018  
Valid up-to: 24 OCT 2019




Quality Registrar Systems



CB-037-MS

**MANAGING OFFICE ADDRESS:**  
Quality Registrar Systems  
P.O. Box :26826  
United Arab Emirates





Tel: +971-2-6714302  
Fax: +971-2-6741449  
www.qrsyst.com

**WORLD WIDE CERTIFICATION**

Quality Registrar Systems is accredited by Dubai Accreditation Department (DAC)  
for the Scope mention on Quality Registrar Systems (QRS) Accreditation Certificate No. CB-037-MS

# Municipality Approval

	Organization Unit: General Projects Department (الوحدة التنظيمية: إدارة الصيانة العامة)		
	Form sheet title:	Material Approval Form (MAF)	
	Doc Ref.	DM_GPD_P3_F10	رقم النموذج:

Submittal No.	591/CIV/SC/13	Rev.	00	Date	02-05-2018	<input checked="" type="checkbox"/> New Submittal.	<input type="checkbox"/> Re-submittal
---------------	---------------	------	----	------	------------	--	---------------------------------------

Project No.	M-2229/5	Project Code		End User	Dubai Municipality
Project Title	Development Works at Warsan Fruit & Vegetable Market, Market 3 Package				
L.E.	Engr Ahmed Rastam	L.A.		MEP Eng.	
Consultant	Al Turath Engineering Consultant		Contractor	Al Turath Al Aseel Contracting L.L.C	
Sub-contractor		Trade	Civil		

Description / Technical Letrate:  
Proposed supplier for **FORMWORK & SCAFFOLDING**

Attachments  Sample.  Technical Data.  QA/QC Reports.  Method Statement.  Others

Area of Application / Location **Slab Zone 3**

Specs Ref.  Dwg. Ref.  BOQ ref.

Origin  Manufacturer Name: **Future Form System**

Local Agent **Future Form System** e-mail / Tel. 04-4542162

**Contractor's Attestation**

Material Submittal Comply with Specifications  Yes.  Alternative.

Details if Alternative: .....

Certified By: **Eger Ahmad Darwish** Signature / Date: **02-05-2018**

**For Consultant**

No Objection

No Objection with Comments

Rejected

Date forwarded to DM: .....

Date Received from DM: **08/5/18**

Comments:  
*Rifa'ah comments on attached sheet dated 08/5/18.*

Consultant Authorized: \_\_\_\_\_ Signature / Date: \_\_\_\_\_

**For Dubai Municipality (DM)**

1. Work may proceed.

2. work may proceed subject to incorporation of comments.

3. Revise & re-submit, work may proceed subject to incorporation of comments.

4. Revise & re-submit, work may not proceed.

5. Rejected.

Comments: .....

DM Authorized: \_\_\_\_\_ Signature / Date: \_\_\_\_\_

**RECEIVING**

AIC, Al Turath Al Aseel Contracting L.L.C

DATE: **10/5/18**

TIME: **12:16**

رقم الإصدار: \_\_\_\_\_

توقيع: \_\_\_\_\_

03 MAY 2018

11-04-2017 تاريخ الإصدار:



# Key Consultant Approval

Contract No.: DMS 138223	EMPLOYEE: NAKHEEL	SCA No.
Proj. No.: DFF103-08900 ENGINEER: Dar Al Handasah (Shair and Partners)	NAKHEEL MEMBER SINCE: 1978 REGISTERED IN THE PROFESSION OF ENGINEERS	PGF-STR-033000-01810
	CONTRACTOR: Gulf Technical Construction Co. LLC	Date: 21-May-16
<b>SUB-CONTRACTOR'S APPROVAL</b>		
1. SUB-CONTRACTOR'S PARTICULARS		
Company Name: Future Form System		
Company Line or Works: Supply of Rebar Coupler		
Address: P.O. Box 52360, Dubai, U.A.E. INTERCOM 3, TEL: 04-4542162, FAX: 04-4542170		
The following prequalifying documents should be enclosed:		
<input type="checkbox"/> Commercial Register <input type="checkbox"/> Foundry Contact <input type="checkbox"/> Summary of Experience <input type="checkbox"/> Financial Status <input type="checkbox"/> Present Works <input type="checkbox"/> Company Staff <input type="checkbox"/> Company Equipment		
2. SUB-CONTRACTED WORKS		
Section of the Works: 033000 - Concrete Works		
BOQ Items		
Total Value of Sub-Contract (in Contract Rates):		
Cumulative Value of Sub-Contracted Works to-date (in Contract Rates):		
Submitted by: <u>Bal Alwasidi</u> Signature:		
3. ENGINEER'S COMMENTS		
<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved As Noted <input type="checkbox"/> Additional Info Required <input type="checkbox"/> Rejected		
Signature:     DATE: 06/06/2016		
CLIENT:		
<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved As Noted <input type="checkbox"/> Additional Info Required <input type="checkbox"/> Rejected		
DATE: 06/06/2016		

Proj. no.: S13037-01000 Package 01-Infrastructure	Employer:	Request No. MAT-SSC-0074 Rev-00 Date: 17-Jun-15
Consultant:	Contractor:	
<b>Submit for Approval of Materials</b>		
1. Material description (one item only on this form): <b>COUPLER SYSTEM</b> (2 Nos. submittal, 2 Nos. CD)		
Area of application: BUILDINGS		
Drawing ref. B.O.Q. Ref. No.:		
Specification Ref.: SECTION 033000 Standards: ASTM A 615		
Attach all relevant technical literature marked to identify relevant description, current Test Certificates, samples as appropriate.		
2. Manufacturer / supplier		
Company Name: FUTURE FORM SYSTEMS		
Address: P.O. BOX 83260, DUBAI, U.A.E. INTERCOM 3, TEL. NO. 974-4386222, EMAIL: FUTUREFORMSYSTEMS@GMAIL.COM		
Local Agent: FUTURE FORM SYSTEMS		
3. Delivery:		
Country of origin: K.S.A		
Availability:		
Delivery: <input checked="" type="radio"/> Locally Manufactured <input type="radio"/> Overseas		
Ex-works/ total duration		
Estimated time of arrival on site		
Program		
Date material required on site		
Latest date for order		
We certify that the above submitted items have been reviewed in detail and are correct and in strict conformity with the contract drawings and specifications except as otherwise stated; also that the material sources indicated above have been reviewed in detail and that they will supply the submitted items in conformity with the above and deliver same timely.		
Submitted by: ENGR. HISHAM ABDULLAHA    Signature:		
4. Engineer's Representative comments:		
<input type="checkbox"/> Approved <input checked="" type="checkbox"/> Approved as Noted <input type="checkbox"/> Revise and Resubmit <input type="checkbox"/> Rejected <input type="checkbox"/> Sample required <input type="checkbox"/> Tests required <input type="checkbox"/> Additional information Required <input type="checkbox"/> Manufacturer's Guarantee Required		
Final approval will be subjected to tensile test result. As per specification section 03, clause 2.3C		
Reviewed by: Munser Badarnah		
Signature:     Date: 17 JUN 2015		
5. Employer's Representative comments:		
Signature: _____    Date: / /		
Approval shall not relieve Contractor of his liabilities under the Contract or constitute authorization of any change to Contract Documents.		

<b>SUBMITTAL TRANSMITTAL SHEET #</b>		199/TR - 0117-R2			
Project Name: JAMAC TWIN RESIDENTIAL TOWERS FOUNDATION TO GRADE	Project No. 199	Date: 08.12.2012	Revision: 2		
Submittal No.: DIVISION 03 - MT-CIV-034-R2 Doc	REBAR MECHANICAL SPLICING COUPLER				
We are sending herewith under separate cover the drawings / documents / samples listed below:					
ITEM NO.	DWG. SPEC. BOQ REF.	DESCRIPTION	TYPE	COPIES	REMARKS
1	BOQ 03.21.00	1. Pre-qualification for Coupler. 2. Company Registration certificate. 3. Method statement for rebar coupler. 4. Location map. 5. Testing of coupler. Attachment: ( Pre-qualification 62 Pages)	OT	3	
1. Title: BO-Shop Drawing, (MR- Samples, OT-Coupler, MR- Manufacturer's Data, QC- Certificates, 11- Test Results, 01- Other				FUTURE	
Supplier / Manufacturer:				FUTURE	
We certify that the documents / materials submitted herewith have been reviewed in detail and are in strict conformance with the contract drawings and specifications except as otherwise stated.					
Contractor Name: ENGR. AHMAD IZZUDDIN				Signature:	
Project Manager				Date: _____	
Design Consultant Review Comments					
Contractor should submit complete test for all the couplers that we witnessed today 25th Dec 2012 at the lab				Consultant Decision	
				Approved	
				Approved As Noted	
				Not Approved	
				Not Required	
Design Consultant (Name): SSE Magdy				Signature:	
Date: 27/12/2012				Rcv'd By: _____	
Conditions or comments made relative to submittals during this review do not relieve the contractor from compliance with the requirements of the Contract. This check is only for review of general conformance with the design concept of the project and general consistency with the information given in the contract documents. The contractor is responsible for confirming and controlling all quantities and dimensions, selecting fabrication processes and techniques of construction, coordinating his work with that of other trades and performing his work in a safe and satisfactory manner.					
COPY TO:					
Head Office <input type="checkbox"/> Consultant <input type="checkbox"/> QS <input type="checkbox"/> Other <input type="checkbox"/>					
Sheet No. _____ of _____					
Received: 8-12-2012 4:30pm					

# Key Consultant Approval

RECEIVED  
27 JAN 2013

SAUDI ARABIA  
Material Submittal (MS)

Project Name : **Dar Al-Yaum Tower Project**

Ref. No. : MS / 003-023 - Rev / 00 Date : 27-Jan-13 Due Date : 10-Feb-13

Material Division / Section : Civil / 03

Specs./BOQ/Dr. Ref. : ---

Material Specified : ---

Material Proposed : Rebar Coupler (BS8110 & ACI 318) for vertical Rebar @ Different Sizes

Manufacturer / Supplier : Manufacturer: FUTURE

Reason for Alternative (If Any) : ---

Material Description : Rebar Coupler (BS8110 & ACI 318) for vertical Rebar @ Different Sizes

Contractor's PM Signature & Date : 27/01/13 Received By RGC Signature & Date : 28 JAN 2013

RECEIVED  
28 JAN 2013

Consultant Comments / Status

Approved  Approved As Noted  Incomplete, Resubmit

Not Approved, Resubmit

*Test random test for the required coupler size to be conducted for tensile / staggered arrangement to be performed on the site for rebar.*

The Contractor shall be responsible for any deviation / omission in respect of the contract documents, unless other wise declare ( writing ) for such deviation and the consultant issue an approval accordingly.

RGC's Representative Signature & Date : a.d. 1/2/13 Received By Manufacturer Signature & Date : ---

Enclsd to list ✓

ABDULELAH AL-MOHAMMA FLUORIDE CONSULTANTS

AL FARAJ ARABIA Consulting Engineer

BOUDL BOUDL 10 1111111111

Boudl Trading - Classic Tower Technical Document Submittal

ST  Elec  Mech  Arch

Date : 6-5-2013 Submittal No: AFDM-ST-242 (REV - 1)

Code & Type to be entered by Alfaraj Arabia (To be entered by consultant)

NO.	Shop Drawings	CT	Tests	As Issued	Approved	Approved As Noted	Review And Resubmit	Not Approved	Resubmit For Info.
NO.	Manufacturer's Data	CT	Certificates	Approved	Approved	Approved	Approved	Approved	Approved
NO.	As Built Drawings	PG	Prequalification	Approved	Approved	Approved	Approved	Approved	Approved
NO.	Method Statement	OT	Others	Approved	Approved	Approved	Approved	Approved	Approved
NO.	Sample								
NO.	Quotations								

No.	Specificat Ion Ref. #	Description	Manufacturer / Supplier	Code & Type	Action Code Consultant
1.		Test Results For COUPLERS "MECHANICAL SPLICING METHOD" TO BE USED FOR THE BEAMS BETWEEN CORE WALLS.	ACES FUTURE		A

TECHNICAL MANAGER Signature: Date: 5/1/13

Signature: Date:

Remarks by Consultant

RECEIVED  
28 JAN 2013

CLASSIC TOWER - RICHIAH - VILLAGE

For consultant Received By: Send By:

Signature: Date: Signature: Date: Signature: Date:

ACES ab Company الشركة العربية للمقاولات والبناء

Messrs: Best Future Concrete Formwork Riyadh - KSA.

09/07/2017 RMR13000521

Subject: Certificate of Test on Steel Couplers Private

Dear Sirs,

1. INTRODUCTION

According to your request No. RMO13000191 dated Feb. 06, 2013, tensile test was carried out on one pair of steel bar piece connected by coupler in the middle brought to our laboratories upon the request of the contractor's representative Mr. Ashraf Roshdy on Feb. 06, 2013. This report presents the tests results.

2. TESTS RESULTS

No.	Description	Diameter of Steel (mm)	Tensile Load At Failure (KN)	Tensile Strength At Failure (MPa)*	Failure Location	ACI 318M/318RM-12.14.3.2 Requirements (Grade 420 Steel)
1	Ø16 mm Coupler	16	144.15	717	Cut of steel bar outside coupler	1.25f <sub>y</sub> =525 MPa
2	Ø20 mm Coupler	20	219.65	699	Cut of steel bar outside coupler	1.25f <sub>y</sub> =525 MPa
3	Ø25 mm Coupler	25	336.00	684	Cut of steel bar outside coupler	1.25f <sub>y</sub> =525 MPa
4	Ø32 mm Coupler	32	564.85	702	Cut of steel bar outside coupler	1.25f <sub>y</sub> =525 MPa

\*Based on nominal diameter.

Checked: Q.M. Approved:

1 of 2 H.A. Station 1 ACES2013RMR2013RMR13000521

Riyadh: P.O. Box 48991 Riyadh 11540. Tel: +966-1152222222. Fax: +966-1152222222. C.C. No. 103888 - C.R. 1010772280 - E-mail: aces@aces-int.com  
 Jeddah: P.O. Box 12399 Jeddah 21582. Tel: +966-1146444444. Fax: +966-1146444444. C.C. No. 103888 - C.R. 403915788 - E-mail: aces@aces-int.com  
 Mecca: P.O. Box 10188 Mecca 21502. Tel: +966-1146444444. Fax: +966-1146444444. C.C. No. 103888 - C.R. 1010772280 - E-mail: aces@aces-int.com  
 Muscat: P.O. Box 498 Muscat - Al-Falaj. Tel: +966-7-1222007. Fax: +966-7-5292271. E-mail: aces@aces-int.com

bsite: www.aces-int.com



# Lab test results

**AL HOTA - STANGER LABORATORIES**  
Independent Testing Laboratories  
and Materials Consultants

مختبرات الحوطي ستانجر  
مختبرات فحص مستقلة  
ومستشار ومواد

**TEST REPORT**

CLIENT **FUTURE SCAFFOLDING**

**TENSILE TESTING OF COUPLERS**

Report date : 06.05.08

Report number : DS-318643	Source : Future Scaffolding
Sample number : DS-318643	Sample location : Site Work
Project number : Not given	Contractor : Future Scaffolding
Project name : Quality Assurance	Sampled by : Client
Project location : Not given	Sampling date/time : 28.04.08 / 19:30 Hrs.
	Sampling method : Random
	Sample delivered by : Client
Consultant : Not given	Date/time sample received : 28.04.08 / 15:45 Hrs.
Client ref./request no. : Not given	Date tested : 30.04.08
Sample description as : Couplers	Date of mill certificate : Not given
Identified by the client : Not given	Heat no : Not given
Local supplier : Not given	Test method : BS EN 10002-1 : 2001
Nominal size : 28 mm	Tested by : ABS

**Test results :**

Specimen ID	Peak Load (kN)	Mode of Failure
DS9 348643	187.68	The rebar was broken

Remarks : None  
Test Method Variation : None  
This report relates only to the sample tested and shall only be reproduced in full and with the written approval of AHS Laboratories.

Joseph Hegu, Laboratory Manager  
Head of Construction Materials Section For Al Hota Stanger Laboratories

Page 1 of 1

تلفون : 3472201 (04) فاكس : 3472227 (04)  
ص.ب. 16756، ديرة، أ.ع.م. تيل : 3472201 (04) فاكس : 3472227 (04)  
E-mail : alhota@emirates.net.ae

ISO 9001:2000

**AL HOTA - STANGER LABORATORIES**  
Independent Testing Laboratories  
and Materials Consultants

مختبرات الحوطي ستانجر  
مختبرات فحص مستقلة  
ومستشار ومواد

**TEST REPORT**

CLIENT **FUTURE SCAFFOLDING**

**TENSILE TESTING OF COUPLERS**

Report date : 06.05.08

Report number : DS-318672	Source : Future Scaffolding
Sample number : DS-318644	Sample location : Site Work
Project number : Not given	Contractor : Future Scaffolding
Project name : Quality Assurance	Sampled by : Client
Project location : Not given	Sampling date/time : 28.04.08 / 19:30 Hrs.
	Sampling method : Random
	Sample delivered by : Client
Consultant : Not given	Date/time sample received : 28.04.08 / 15:45 Hrs.
Client ref./request no. : Not given	Date tested : 30.04.08
Sample description as : Couplers	Date of mill certificate : Not given
Identified by the client : Not given	Heat no : Not given
Local supplier : Not given	Test method : BS EN 10002-1 : 2001
Nominal size : 28 mm	Tested by : ABS

**Test results :**

Specimen ID	Peak Load (kN)	Mode of Failure
DS9 348644	308.90	The rebar was broken

Remarks : None  
Test Method Variation : None  
This report relates only to the sample tested and shall only be reproduced in full and with the written approval of AHS Laboratories.

Joseph Hegu, Laboratory Manager  
Head of Construction Materials Section For Al Hota Stanger Laboratories

Page 1 of 1

تلفون : 3472201 (04) فاكس : 3472227 (04)  
ص.ب. 16756، ديرة، أ.ع.م. تيل : 3472201 (04) فاكس : 3472227 (04)  
E-mail : alhota@emirates.net.ae

ISO 9001:2000

**AL HOTA - STANGER LABORATORIES**  
Independent Testing Laboratories  
and Materials Consultants

مختبرات الحوطي ستانجر  
مختبرات فحص مستقلة  
ومستشار ومواد

**TEST REPORT**

CLIENT **FUTURE SCAFFOLDING**

**TENSILE TESTING OF COUPLERS**

Report date : 06.05.08

Report number : DS-318673	Source : Future Scaffolding
Sample number : DS-318645	Sample location : Site Work
Project number : Not given	Contractor : Future Scaffolding
Project name : Quality Assurance	Sampled by : Client
Project location : Not given	Sampling date/time : 28.04.08 / 19:30 Hrs.
	Sampling method : Random
	Sample delivered by : Client
Consultant : Not given	Date/time sample received : 28.04.08 / 15:45 Hrs.
Client ref./request no. : Not given	Date tested : 30.04.08
Sample description as : Couplers	Date of mill certificate : Not given
Identified by the client : Not given	Heat no : Not given
Local supplier : Not given	Test method : BS EN 10002-1 : 2001
Nominal size : 33 mm	Tested by : ABS

**Test results :**

Specimen ID	Peak Load (kN)	Mode of Failure
DS9 348645	497.88	The rebar was broken

Remarks : None  
Test Method Variation : None  
This report relates only to the sample tested and shall only be reproduced in full and with the written approval of AHS Laboratories.

Joseph Hegu, Laboratory Manager  
Head of Construction Materials Section For Al Hota Stanger Laboratories

Page 1 of 1

تلفون : 3472201 (04) فاكس : 3472227 (04)  
ص.ب. 16756، ديرة، أ.ع.م. تيل : 3472201 (04) فاكس : 3472227 (04)  
E-mail : alhota@emirates.net.ae

ISO 9001:2000

# Company Information

## FUTURE Form systems

Plot 34023, Dubai industrial city  
PO Box 52360, Dubai - UAE

Tel: 04 454 21 62 Fax 04 454 21 70

Website: [www.Futureformwork.com](http://www.Futureformwork.com)

**Trade Name:** Future scaffolding and Aluminium trading

License no. 563713

Register no. 71113


DCCI no. 92879

**Trade Name:** Future scaffolding and Aluminium Industries

License no. 570634

Register no. 74756

DCCI no. 98668



[www.Futureformwork.com](http://www.Futureformwork.com)

